SECTION 01 55 26

STREET USE PERMIT AND MODIFICATIONS TO TRAFFIC CONTROL

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Administrative procedures for:
 - a. Street Use Permit
 - b. Modification of approved traffic control
 - c. Removal of Street Signs
- B. Deviations from this City of Fort Worth Standard Specification
 - 1. None.
- C. Related Specification Sections include, but are not necessarily limited to:
 - 1. Division 0 Bidding Requirements, Contract Forms and Conditions of the Contract
 - 2. Division 1 General Requirements
 - 3. Section 34 71 13 Traffic Control

1.2 PRICE AND PAYMENT PROCEDURES

- A. Measurement and Payment
 - 1. Work associated with this Item is considered subsidiary to the various Items bid. No separate payment will be allowed for this Item.

1.3 REFERENCES

- A. Reference Standards
 - 1. Reference standards cited in this specification refer to the current reference standard published at the time of the latest revision date logged at the end of this specification, unless a date is specifically cited.
 - 2. Texas Manual on Uniform Traffic Control Devices (TMUTCD).

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Traffic Control
 - 1. General
 - a. When traffic control plans are included in the Drawings, provide Traffic Control in accordance with Drawings and Section 34 71 13.
 - b. When traffic control plans are not included in the Drawings, prepare traffic control plans in accordance with Section 34 71 13 and submit to City for review.
 - 1) Allow minimum 10 working days for review of proposed Traffic Control.
- B. Street Use Permit
 - 1. Prior to installation of Traffic Control, a City Street Use Permit is required.
 - a. To obtain Street Use Permit, submit Traffic Control Plans to City Transportation and Public Works Department.

- 1) Allow a minimum of 5 working days for permit review.
- 2) Contractor's responsibility to coordinate review of Traffic Control plans for Street Use Permit, such that construction is not delayed.
- C. Modification to Approved Traffic Control
 - 1. Prior to installation traffic control:
 - a. Submit revised traffic control plans to City Department Transportation and Public Works Department.
 - 1) Revise Traffic Control plans in accordance with Section 34 71 13.
 - 2) Allow minimum 5 working days for review of revised Traffic Control.
 - 3) It is the Contractor's responsibility to coordinate review of Traffic Control plans for Street Use Permit, such that construction is not delayed.
- D. Removal of Street Sign
 - 1. If it is determined that a street sign must be removed for construction, then contact City Transportation and Public Works Department, Signs and Markings Division to remove the sign.
- E. Temporary Signage
 - 1. In the case of regulatory signs, replace permanent sign with temporary sign meeting requirements of the latest edition of the Texas Manual on Uniform Traffic Control Devices (MUTCD).
 - 2. Install temporary sign before the removal of permanent sign.
 - 3. When construction is complete, to the extent that the permanent sign can be reinstalled, contact the City Transportation and Public Works Department, Signs and Markings Division, to reinstall the permanent sign.
- F. Traffic Control Standards
 - 1. Traffic Control Standards can be found on the City's Buzzsaw website.
- 1.5 SUBMITTALS [NOT USED]
- 1.6 ACTION SUBMITTALS/INFORMATIONAL SUBMITTALS [NOT USED]
- 1.7 CLOSEOUT SUBMITTALS [NOT USED]
- 1.8 MAINTENANCE MATERIAL SUBMITTALS [NOT USED]
- 1.9 QUALITY ASSURANCE [NOT USED]
- 1.10 DELIVERY, STORAGE, AND HANDLING [NOT USED]
- 1.11 FIELD [SITE] CONDITIONS [NOT USED]
- 1.12 WARRANTY [NOT USED]
- PART 2 PRODUCTS [NOT USED]
- PART 3 EXECUTION [NOT USED]

END OF SECTION

Revision Log		
DATE	NAME	SUMMARY OF CHANGE